



**Paving Key**

1. Dark Multistock in Herringbone - 2.07m<sup>2</sup>
2. Mixed Stock in Running Bond - 0.8m<sup>2</sup>
3. Paving Wire Cuts in English Bond - 6.3m<sup>2</sup>
4. Pink Granite Setts in Stretcher Bond - 1.3m<sup>2</sup>
5. Mixed Stock in Stack Bond - 1.16m<sup>2</sup>
6. Red Stocks in English Bond - 5.62m<sup>2</sup>
7. Pink Granite Setts in Stretcher Bond - 2.27m<sup>2</sup>
8. Yellow Stock in Herringbone - 2.26m<sup>2</sup>
9. Paving Wire Cuts in English Bond - 2m<sup>2</sup>
10. Yellow stock in Stretcher Bond - 0.7m<sup>2</sup>
11. Dark Multistocks in Herringbone - 3.3m<sup>2</sup>
12. Mixed Stock in Stack Bond - 2.32m<sup>2</sup>

Total Paving area = 30.2m<sup>2</sup>  
New Grass area = 70m<sup>2</sup>

The exact measurements of each paving element will be finalised on site with the contractor.

DO NOT SCALE FROM THIS DRAWING  
ALL DIMENSIONS TO BE CHECKED ON SITE PRIOR TO THE START OF ANY WORK AND ANY DISCREPANCIES NOTIFIED IN WRITING  
REFER TO ENGINEER'S DRAWINGS FOR ALL STRUCTURAL, HEATING, LIGHTING, POWER, EXTERNAL AND UNDERGROUND DRAINAGE AND VENTILATION INFORMATION  
ALL BUILDING WORKS COMPLY IN ALL RESPECTS TO CURRENT BUILDING STANDARDS FOR COUNTRY IN WHICH SITE IS LOCATED

Revision Date Revision Note

Job Reference <b>1801</b>	Drawing Number <b>P(GA)100</b>	Revision
Scale <b>1:100</b>	Paper Size <b>A3</b>	

Drawing Name  
**Proposed Plan**

Drawn By <b>JS</b>	Checked <b>BT</b>	Date Drawn <b>04/10/18</b>
-----------------------	----------------------	-------------------------------

Project  
**Langthorne Community Junction**

Client  
**Waltham Forest Council**

Element 1 is kept in level with existing paving on Brierley Road. Elements 2 and 3 are stepped at 180mm increments. Element 3 is level with element 4

Paving elements 10-12 will be on the same level as the grass area and the existing pavement of Langthorne Road

Element 9 will be raised 180mm higher than the level of elements 10-12 and surrounding grass

Element 4 is kept in the same level as the surrounding grass. Element 5 and 6 go up 180mm at each level. Element 6 is level with the surrounding grass on the North edge of the step.

Element 7 is level with surrounding grass

Element 8 will be raised 180mm from the surrounding heights of the grass and element 7

Approximate route of underground electric cable. Please see power drawings for further information

BRIERLEY ROAD

LANGTHORNE ROAD

Existing Maple Tree

Turfed Area